



December 21, 2018

To whom it may concern:

The Colfax County Board of Commissioners will be receiving sealed bids for the project enclosed. Please contact Mainelli Wagner & Associates, Inc. for copies of the Plans and Specifications. The Bids are due by 10:30 a.m. on January 29, 2019. The Bids will be opened on January 29, 2019 at 10:30 a.m.

If you have any questions in regard to this project or the enclosed information, please contact Mainelli Wagner & Associates prior to the Bid Letting.

Jeff Wagner  
Mainelli Wagner & Associates, Inc  
6920 Van Dorn, Suite "A"  
Lincoln, NE 68506  
Phone: 402-421-1717

MAINELLI WAGNER & ASSOCIATES, INC.

Jeff Wagner, P.E.

# **BID DOCUMENTS AND SPECIFICATIONS**

## **Colfax County 2019 Culvert Installation**

**Schuyler Northwest, C-19(497)  
Structure No. C001902605**

**Clarkson Southwest, C-19(500)  
Section 13/14-T19N-R2E**

**Colfax County, Nebraska**

## NOTICE TO BIDDERS

Sealed bids will be received by the Colfax County Clerk until 10:30 a.m. on January 29, 2019 for the installation of corrugated metal pipes with steel headwalls attached, wingwalls and other related incidental work at two sites in Colfax County. Colfax County will furnish and deliver the culvert pipes (with headwalls attached) and wingwall materials to the project sites. The project sites are located: (497) – Road M between Road 3 and Road 4 and (500) – Road 6 between Road P and Road Q, both in Colfax County, Nebraska. The bids will be opened on January 29, 2019 at 10:30 a.m.

The project is referred to as “Colfax County 2019 Culvert Installation: C-19(497) and C-19(500)” and shall include all labor, materials, transportation and equipment required to install: (497) – twin 120” x 84’ on a 20 deg. Skew (lhb) and (500) – twin 84” x 49’ on a 0 deg. skew, both corrugated metal pipes with steel headwalls attached and wingwalls.

Copies of the Bid specifications and plans are open to public inspection at the office of the Colfax County Highway Dept., 466 Road 10, Schuyler, NE 68661. A set of documents may be obtained from Mainelli Wagner & Associates, Inc. 6920 Van Dorn Street, Suite “A”, Lincoln, NE 68506 (Phone: 402-421-1717) for a non-refundable fee of \$30.00. All Bid Proposals must be submitted on the forms furnished with the Bid Documents.

The sealed bids may be mailed or delivered to the Colfax County Clerk, 411 E. 11th Street, Schuyler, NE 68661, and should be plainly marked as, “Colfax County 2019 Culvert Installation: C-19(497) and C-19(500)”.

Along with its Bid Proposal, each bidder shall submit an unconditional Bid Bond or Certified Check made payable to the County Treasurer of Colfax County, Nebraska, in an amount equal to five (5) percent of the Bid Proposal. Also, each bidder is to include an estimated completion date for each site with their Bid Proposal. The desired completion date of both sites is May 31, 2019. The required completion date of each site shall be the earlier of the date indicated in the bid proposal or 28 calendar days after beginning work at the site. Additional days due to weather may be added at the discretion of the Engineer. No project can be started without the intent to complete that site without delay from the other site, therefore, the Contractor will not be allowed to start the removals at a site unless they have committed a crew to complete the work at that site.

Within ten (10) days following the award of the Contract, the successful bidder shall furnish a surety bond or bonds in an amount equal to or greater than the full amount of the contract. The surety and form of the bonds are subject to the acceptance by the Colfax County Board of Commissioners.

The Colfax County Board of Commissioners reserves the right to reject any and all bids or to waive any irregularities in bids received. Award of the Contract will be in accordance with the County Purchasing Act’s competitive bidding considerations as set forth in Neb.Rev.Stat. §§ 23-3110 to 23-3114. Colfax County is an Equal Opportunity Employer.

---

Colfax County Clerk

**PROPOSAL FOR COLFAX COUNTY 2019 CULVERT INSTALLATION:  
C-19(497) AND C-19(500)**

COLFAX COUNTY, NEBRASKA

Board of County Commissioners  
Colfax County Courthouse  
Schuyler, Nebraska 68661

Gentlemen:

\_\_\_\_\_, (Contractor) after reviewing these Bid Documents and Specifications in full, propose to furnish all labor, transportation, materials and equipment and all other miscellaneous items required to construct the project as shown at the following unit prices:

C-19(497): TWIN 120" x 84' CORRUGATED METAL PIPES ON A 20 DEG. SKEW (LHB)

<u>ITEM NO.</u>	<u>PLAN QUANTITY</u>	<u>ITEM DESCRIPTION</u>	<u>UNITS</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
1-1.	1.000	Mobilization	Lump Sum	_____	_____
1-2.	1.000	Site Preparation	Lump Sum	_____	_____
1-3.	1,150.000	Excavation, Established Quantity	Cu. Yds	_____	_____
1-4.	168.000	Install 120" Corrugated Metal Pipe	Lin. Ft.	_____	_____
1-5.	4.000	Install Steel Wingwall	Each	_____	_____
1-6.	40.000	Fabric Silt Fence, Low Porosity	Lin. Ft.	_____	_____
1-7.	200.000	Temporary Silt Fence	Lin. Ft.	_____	_____
1-8.	2,468.000	Earthwork Measured in Embankment	Cu. Yds.	_____	_____
1-9.	95.000	Gravel Surface Course	Tons	_____	_____
1-10.	0.600	Covercrop Seeding	Acres	_____	_____
1-11.	2,904.000	Erosion Control, Class "1D"	Sq. Yds.	_____	_____

1-12.	415.000	Fabric Silt Fence, Low Porosity	Lin. Ft.	_____	_____
-------	---------	------------------------------------	----------	-------	-------

**1T. TOTAL FOR C-19(497)** \_\_\_\_\_

C-19(500): TWIN 84" x 49' CORRUGATED METAL PIPES ON A 0 DEG. SKEW

ITEM NO.	PLAN QUANTITY	ITEM DESCRIPTION	UNITS	UNIT PRICE	AMOUNT
2-1.	1.000	Mobilization	Lump Sum	_____	_____
2-2.	1.000	Site Preparation	Lump Sum	_____	_____
2-3.	361.000	Excavation, Established Quantity	Cu. Yds	_____	_____
2-4.	98.000	Install 84" Corrugated Metal Pipe	Lin. Ft.	_____	_____
2-5.	4.000	Install Steel Wingwall	Each	_____	_____
2-6.	40.000	Fabric Silt Fence, Low Porosity	Lin. Ft.	_____	_____
2-7.	200.000	Temporary Silt Fence	Lin. Ft.	_____	_____
2-8.	694.000	Earthwork Measured in Embankment	Cu. Yds.	_____	_____
2-9.	47.000	Gravel Surface Course	Tons	_____	_____
2-10.	0.200	Covercrop Seeding	Acres	_____	_____
2-11.	968.000	Erosion Control, Class "1D"	Sq. Yds.	_____	_____
2-12.	206.000	Fabric Silt Fence, Low Porosity	Lin. Ft.	_____	_____

**2T. TOTAL FOR C-19(500)** \_\_\_\_\_

**TOTAL FOR PROJECT (1T+2T)** \_\_\_\_\_

**All Project Sites will be awarded to one Contractor based on the TOTAL FOR PROJECT. The County reserves the right to construct any or all of the Roadway Items.**

We understand that this will be a lump sum contract and the total contract amount will be obtained by multiplying the Plan Quantities by the associated Unit Prices.

If awarded the contract, we will furnish a surety bond and certificates of insurance as indicated in the Contract Documents. We will not exclude any Proprietor/Partner/ Executive Officer/Member from the workers compensation and employers liability coverage of the insurance certificate.

As specified in the Notice to Bidders, we hereby submit this **BID BOND CERTIFIED CHECK** in the amount of \$ \_\_\_\_\_ (5% of total bid for all sites). This bond will become the property of Colfax County if an award is offered within thirty days after the bid opening and we, as the successful bidder, fail to enter into a contract with Colfax County.

Start of Construction Date for C-19(497): \_\_\_\_\_

End of Construction Date for C-19(497): \_\_\_\_\_

Start of Construction Date for C-19(500): \_\_\_\_\_

End of Construction Date for C-19(500): \_\_\_\_\_

Sincerely,

\_\_\_\_\_ (printed name)

\_\_\_\_\_ (signature)

\_\_\_\_\_ (title)

\_\_\_\_\_ (company)

\_\_\_\_\_ (address)

\_\_\_\_\_ (telephone)